Site Name	Equip Position	In Service YR	Need	Project Number	Planning Criterion	Total Cost	Non-Wires Alternative	Peak Load YR 1	Peak Load YR 2	Peak Load YR 3	Peak Load YR 4	Peak Load YR 5	Line Location on Exhibit 4
Southington 4C	4C-7X	TBD	Capacity	CS00382	DSPG, CLF-SC-023 Att. 1	$ 6,443,618	2.5MW/5MWh BESS	N/A	N/A	N/A	N/A	N/A	N/A
Hopewell 22R	22R-2X_22R-3X	TBD	Capacity	CS00383	DSPG, CLF-SC-023 Att. 1	$ 10,150,980	8.7MW/ 42MWh BESS	N/A	N/A	N/A	N/A	N/A	N/A
Beacon Falls 11N	11N-1X_11N-2X	TBD	Capacity	CS00392	DSPG, CLF-SC-023 Att. 1	$ 9,255,948	2.5MW/6MWh BESS	N/A	N/A	N/A	N/A	N/A	N/A
Bokum 15L	15L-2X_15L-3X	2024	Capacity	CS00365	DSPG, CLF-SC-023 Att. 1	$ 34,709,225	10MW/ 40MWh BESS	74.9	N/A	N/A	N/A	N/A	Included within in Supplemental Filing for January to June 2026. See Project Specific - Pre 2022 - Line: 961.
Carmel Hill 11S	11S-2X	2022	Capacity	CS00284	DSPG, CLF-SC-023 Att. 1	$ 11,066,789	N/A	20.1	21.9	24.2	N/A	N/A	Project Specific - Pre 2022 - Line: 801
Ridgefield 22N	22N-2X_22N-3X	2022	Capacity	CS00516	DSPG, CLF-SC-023 Att. 1	$ 10,335,999	N/A	53.9	55.9	60.9	N/A	N/A	Project Specific - Pre 2022 - Line: 872
Sandy Hook 37F	37F-2X	2022	Capacity	CS00261	DSPG, CLF-SC-023 Att. 1	$ 12,343,384	N/A	24.2	24.6	27.1	N/A	N/A	Project Specific - Pre 2022 - Line: 792
Mansfield 12J	12J-4X_12J-3X	2022	Capacity	CS00166	SYSPLAN010	$ 22,145,225	N/A	12.3	25.6	25.1	N/A	N/A	Project Specific - Pre 2022 - Line: 742
Northeast Simsbury 43F	43F-2X	2019	Capacity	CS00273	SYSPLAN010	$ 10,543,303	N/A	28.9	26.8	31.0	29.5	36.5	Project Specific - Pre 2022 - Line: 796
Rood Avenue 24J	24J-3X	2019	Capacity	CS00272	SYSPLAN010	$ 9,185,847	N/A	26.0	27.5	25.7	25.3	43.3	Project Specific - Pre 2022 - Line: 795
Stepstone 35L	35L-2X	2019	Capacity	CS00247	SYSPLAN010	$ 9,485,921	N/A	40.7	32.8	34.3	30.9	32.8	Project Specific - Pre 2022 - Line: 780
Greenwich 28F	28F-1X_28F-2X	2019	Capacity	201444	SYSPLAN010	$ 21,829,207	N/A	51.9	52.2	47.4	49.3	53.3	Project Specific - Pre 2022 - Line: 929
Scitico 27H	27H-3X	2018	Capacity	CS00061	SYSPLAN010	$ 9,143,034	N/A	64.4	69.4	74.1	79.6	68.2	Project Specific - Pre 2022 - Line: 703

Year	Southington_ 4C_13.8
2008	39.5
2009	21.1
2010	60.9
2011	59.9
2012	58.6
2013	59.7
2014	52.3
2015	55.9
2016	57.5
2017	55.8
2018	59.0
2019	59.1
2020	57.7
2021	55.6
2022	*60.4*
2023	*60.5*
2024	*60.8*
2025	*61.1*
2026	*61.5*
2027	*61.9*
2028	*62.4*
2029	*63.0*
2030	*63.6*
2031	*64.3*
22-31 CAG	0.71%

Year	Hopewell _22R
2008	54.0
2009	61.1
2010	60.8
2011	67.7
2012	66.0
2013	65.5
2014	55.1
2015	55.3
2016	58.1
2017	55.7
2018	61.7
2019	60.4
2020	62.7
2021	64.8
2022	*68.7*
2023	*68.9*
2024	*69.2*
2025	*69.6*
2026	*70.1*
2027	*70.6*
2028	*71.1*
2029	*71.7*
2030	*72.4*
2031	*73.3*
22-31 CAGR	0.71%

Year	Beacon_Falls_11N
2008	67.9
2009	51.8
2010	60.2
2011	52.2
2012	51.0
2013	51.9
2014	44.3
2015	47.4
2016	48.2
2017	47.3
2018	52.7
2019	50.2
2020	52.4
2021	51.5
2022	*57.8*
2023	*57.9*
2024	*58.1*
2025	*58.5*
2026	*58.8*
2027	*59.2*
2028	*59.6*
2029	*60.1*
2030	*60.6*
2031	*61.3*
22-31 CAGR	0.66%

Year	Bokum_15L
2008	66.9
2009	73.3
2010	76.5
2011	74.8
2012	52.6
2013	75.4
2014	65.3
2015	66.9
2016	74.5
2017	75.8
2018	74.2
2019	73.5
2020	76.6
2021	*80.6*
2022	*81.1*
2023	*81.5*
2024	*81.8*
2025	*82.1*
2026	*82.5*
2027	*82.8*
2028	*83.3*
2029	*83.8*
2030	*84.3*
21-30 CAGR	0.51%

Year	Carmel_Hill_11S
2008	16.2
2009	15.3
2010	17.9
2011	20.5
2012	21.0
2013	22.5
2014	18.1
2015	19.5
2016	22.1
2017	19.5
2018	22.4
2019	22.7
2020	24.0
2021	*24.7*
2022	*24.8*
2023	*24.9*
2024	*24.9*
2025	*25.0*
2026	*25.1*
2027	*25.2*
2028	*25.3*
2029	*25.4*
2030	*25.6*
21-30 CAGR	0.37%

Year	Ridgefield_22N
2008	62.9
2009	65.0
2010	59.3
2011	60.6
2012	61.4
2013	59.8
2014	50.1
2015	53.0
2016	56.6
2017	62.5
2018	58.8
2019	58.0
2020	58.1
2021	*59.9*
2022	*60.4*
2023	*60.7*
2024	*60.9*
2025	*61.1*
2026	*61.4*
2027	*61.7*
2028	*62.0*
2029	*62.4*
2030	*62.8*
21-30 CAGR	0.52%

Year	Sandy_Hook_37F
2007	9.0
2008	9.2
2009	13.0
2010	14.6
2011	15.8
2012	14.6
2013	15.7
2014	13.1
2015	13.7
2016	26.6
2017	*28.1*
2018	*28.1*
2019	*28.1*
2020	*28.0*
2021	*27.9*
2022	*27.9*
2023	*27.8*
2024	*27.8*
2025	*27.7*
2026	*27.6*
17-26 CAGR	-0.20%

Year	Mansfield_12J_27.6
2008	16.9
2009	14.7
2010	16.3
2011	14.2
2012	16.7
2013	18.2
2014	17.8
2015	16.7
2016	24.8
2017	16.8
2018	17.2
2019	17.4
2020	15.6
2021	*16.5*
2022	*16.6*
2023	*16.6*
2024	*16.6*
2025	*16.7*
2026	*16.7*
2027	*16.7*
2028	*16.8*
2029	*16.9*
2030	*16.9*
21-30 CAGR	0.27%

Earliest Available

Year	Scitico_27H
2007	83.7
2008	78.5
2009	64.6
2010	85.5
2011	77.8
2012	76.9
2013	75.4
2014	64.8
2015	68.4
2016	62.0
2017	*72.2*
2018	*74.6*
2019	*74.7*
2020	*74.5*
2021	*74.6*
2022	*74.9*
2023	*75.0*
2024	*75.0*
2025	*75.0*
2026	*75.1*
17-26 CAGR	0.45%

Earliest Available

Year	Stepstone_35L
2007	N/A
2008	N/A
2009	26.0
2010	30.9
2011	28.9
2012	28.5
2013	28.9
2014	25.4
2015	25.2
2016	26.5
2017	*29.3*
2018	*29.4*
2019	*29.4*
2020	*29.3*
2021	*29.3*
2022	*29.4*
2023	*29.4*
2024	*29.4*
2025	*29.3*
2026	*29.3*
17-26 CAGR	0.01%

Earliest Available

Year	Rood_Ave_24J
2007	9.7
2008	9.0
2009	26.3
2010	35.8
2011	31.1
2012	35.6
2013	31.1
2014	25.7
2015	27.2
2016	28.0
2017	*32.1*
2018	*32.2*
2019	*32.1*
2020	*32.0*
2021	*31.9*
2022	*31.9*
2023	*31.9*
2024	*31.8*
2025	*31.7*
2026	*31.7*
17-26 CAGR	-0.17%

Earliest Available

	Northeast_Simsbury_4
Year	3F
2007	31.0
2008	32.3
2009	27.3
2010	29.2
2011	33.7
2012	33.4
2013	33.8
2014	28.1
2015	29.1
2016	30.9
2017	*32.1*
2018	*32.2*
2019	*32.1*
2020	*32.0*
2021	*31.9*
2022	*31.9*
2023	*31.9*
2024	*31.8*
2025	*31.7*
2026	*31.7*
17-26 CAGR	-0.15%