Project #	Name of Project	Projected Date of Need/Timeline for improvement	Estimated Distribution Investment Cost	Project Justification	EDC Proposed NWS Solicitation?	Proposed Preliminary RFI?	Notes	Project scope and Key materials (e.g., transformer, etc.)	Identification of project risks (e.g., potential for delays or cost overruns)
Unlikely NWS Solicitation Opportunities (Other Planned Investments OVER $500,000, (i.e. Asset Condition, Maintenance, and Safety Projects)									
CD02211	13K57, 13K49 ROW Removal	2026	$3.6M	Asset Condition	NO	NO	Full CPAC Approved Wires & Poles	Project addresses the complete asset removal of poles and conductors in the Right of Way (ROWs) in Stonington, CT Major Materials: • Matting	•Customer Permission / Siting Council / Municipal approvals •Internal construction resources not available to perform the work •Materials Shortage or long lead times
CD02229	South Meadow, 145 PILC Cable Replacement Rank 7	2026	$4.9M	Asset Condition	NO	NO	Full CPAC Approved Wires & Poles	Replace the remaining paper-insulated lead covered (PILC) cable on the South Meadow 145 circuit. Major Materials: • 23,100' of 500 kcmil CU EPR 25kV cable	•Customer Permission / Siting Council / Municipal approvals •Internal construction resources not available to perform the work •Materials Shortage or long lead times
CD02393	2N18 PILC	2026	$5.5M	Asset Condition	NO	NO	Full CPAC Approved Wires & Poles	Replace the remaining of paper-insulated lead covered (PILC) cable on the Northwest Hartford 2N18 circuit. Major Materials: • 22,859' of 500 kcmil 25kV CU EPR cable	•Customer Permission / Siting Council / Municipal approvals •Internal construction resources not available to perform the work •Materials Shortage or long lead times
CS00606	Glenbrook 1K-2X Transformer Replacement	2026	$10.1M	Asset Condition	NO	NO	Full EPAC Approved	Replace the existing 1K-2X 115/13.2kV 46.7MVA transformer with a new 115/13.2kV 62.5MVA transformer and add a mobile transformer position to the station. Major Materials: • 115/13.2kV 62.5MVA Transformer 13.2kV 3-phase Neutral Reactor SF6 115kV Circuit Breaker 115kV 3000A MOD	•Outage Constraints/Availability Equipment/Material Delivery •Internal construction resources not available to perform the work •Mobile transformer to mitigate SCLL concerns •Removal of Unforeseen Environmental concerns
CS00503	East Meriden 21P Switchgear Replacement	2028	$20.1M	Asset Condition	NO	NO	Full EPAC Approved	Replace the existing 13.8kV Switchgear associated Circuit Breakers, Protection Equipment and Station Service Transformers. Major Materials: 2 Sections of Double Bus Switchgear including a total of 34 cubicles, 2 transformers, 12 feeder breakers, and associted controls and relaying 2-115kV Circuit Switchers 115kV Motor Operated Disconnect 3-50 kVA Station Service Transformers	•Outage Constraints/Availability Equipment/Material Delivery Siting Council / Municipal approvals •Internal construction resources not available to perform the work •Mobile transformer to mitigate SCLL concerns •Removal of Unforeseen Environmental concerns
Unlikely NWS Solicitation Opportunities (All Other Planned Investments Under $500,000, including Unknown and Known Priority Investments Required within a Year)									